


#5 BAR AT MID DEPTH. SEE DETAIL S-15 PLAN VIEW FOR DIMENSIONS.

DIAMETER OF THE CLEANOUT PIPE MUST BE THE SAME AS THE MAIN LINE DIAMETER



ELEVATIONS
N.T.S.

NOTES:

A- STANDARD ADJUSTABLE CLEANOUT HEAVY DUTY CAST IRON 12" BOX FRAME (TOP SECTION ONLY) . IT MUST CONFORM TO THE REQUIREMENTS OF AASHTO M 105-06/ASTM A48 CLASS 35B (GRAY IRON CASTING) . THE FRAME SHALL NOT REST ON TOP OF THE PVC LATERAL.

- 1- FOR PIPES LARGER THAN 10" DIA., A STANDARD MANHOLE COVER MUST BE USED.
- 2- CLEANOUT MUST HAVE THE "SEWER" EMBOSSED IN LID.

B- INSTALL A CONCRETE CL 3000 COLLAR WHEN CO IS GOING TO BE LOCATED OUTSIDE OF PAVED AREAS.

C- BEDDING AND BACKFILL MUST CONFORM WITH THE SAME REQUIREMENT AS A SEWER LINE (SEE CITY'S EDS) .


D- 45° BEND

E- WYE.

"ADJACENT TO THE DRIVEWAY" APPLIES TO ANY SANITARY SEWER LATERAL LOCATED WITHIN 12 FEET OF THE EDGE OF THE DRIVEWAY.

SAME AS ABOVE

DIAMETER OF THE CLEANOUT PIPE MUST BE THE SAME AS THE MAIN LINE DIAMETER



CITY OF RICHMOND HILL
STANDARD CONSTRUCTION
DETAIL

S-14

DATE:
MARCH, 2019

CLEANOUT ADJUSTMENT TO GRADE ADJACENT TO DRIVEWAYS